

## Tender document

### **CATEGORY B: CIVIL/RENOVATION WORK:**

**Refurbishment of Workshops, refurbishment of Computer Centres, classroom repairs, flooring and False Ceiling, Environmental Degradation Prevention of Existing Academic Buildings;**

#### **Item 1:-**

Class rooms platform renovation

(a) Upper surface

Approximate area 3500 sq ft

**Specifications:-** Vitrified Scratch proof heavy duty/non slippery floor tiles (1'\*1') 1 feet \* 1 feet, Make Johnson or Spenza

(b) Side surface

approximate area 1000 sq ft

**Specifications:-** Glazed tiles size (1'\*8") 1 feet \* 8 inches Johnson/spenza

#### **Item2:-**

False ceiling

approximate area (22800 sq ft)

**Specifications :-** P/F Armstrong false ceiling system (prima fine fissured micro look) Grids of 600 \* 600 mm with GI ceiling frame work with prima fine fissured ceiling tiles 12 mm thick of 600 \* 600 mm, micro look having 55 NRC and 95% RH and 83% LR

#### **Item3:-**

covering of workshop roof with no 1 tile with two inch mud base

approximate area 13000 sq ft

**Specifications:-** 1 no tile with size (9"\*4.6"\*2")

#### **Item 4:-**

OBD/distemper of class rooms and tutorials ( previously white wash/Lime)

approximate area 60500 sq ft

**Specifications:-** OBD/distemper of Nerolac/Asian standard brands